Republic of the Philippines

## OFFICE OF THE SOLICITOR GENERAL

134 Amorsolo St., Legaspi Village Makati City

## **PURCHASE ORDER**

Supplier:

INNOVALITE INC.

Lot 1F Jenny's Avenue corner Pearl St. Pasig Greenland Subdivision

Rosario, Pasig City

TIN: 008-398-122-000

Account No.: 1641-1049-37

Bank:

Landbank - C. Raymundo Ave.

Telephone: (02) 8628-0605 / 8642-4033

(02) 7915-2145 Fax:

Mode of Procurement: Public Bidding

021-12-197

December 16, 2021

P.O. #

Date:

Gentlemen:

Address:

Place of Delivery:  OFFICE OF THE SOLICITOR GENERAL  Date of Delivery:			Delivery Term: w/n Sixty (60) days upon receipt of NTP  Payment Term: 15% mobilization and payment of 85% progress billing as stated in the TOR w/in 30 days upon final acceptance (Bank to Bank)			
Stock No.		Purchase of Acoustic Ceiling Boards, Delivery, Dismantling, and Installation at the OSG Extension Offices of Office of the Solicitor General located at APMC and Montepino Buildings, Legaspi Village, Makati City  IMC ACOUSTIC CEILING BOARD  Mineral Fiber Acoustic Ceiling Board Fissured 5/8" x 2ft x 4ft - 2,530pieces Quantity (estimated): 2,530 pcs Price per piece (inclusive of VAT): Php 391.00  Material: Mineral fibers mixed with the wet process Surface Coating: Quality Vinyl Emulsion Paint Color: White Density: 350-420kg/m3 Corner Treatment: Square, Lay-in tegular Acoustic Coefficient: 0.4 - 0.6  Office location for the installation of acoustic ceiling boards: APMC Building: Ground Floor Felicisimo Feria Division (Unit 1-A and 1-C), 230pcs Planning Division (Unit 1-E), 100pcs 2nd Floor Rafael Corpuz Division (Unit 2-B), 230pcs Docket Management Service (Unit 2-A), 215pcs 3rd Floor Felix A. Bautista Division (Unit 3-C and 3-D), 215pcs Querube Makalintal Division (Unit 3-A and 3-B), 230 pcs. 4th Floor Special Committee on Naturalization (Unit 4-D), 150 pcs. Arturo Alafriz Division (Unit 5-C and 5-D), 215 pcs. George Harvey Division (Unit 5-C and 5-D), 215 pcs. George Harvey Division (Unit 5-C and 5-D), 215 pcs.	progres final ac	ent Term: 15% mobilizations shilling as stated in the Teceptance (Bank to Bank)	on and payi	0 days upon
		Ignacio Villamor Division (Unit 6-A), 230 pcs.     Juan Liwag Division (Unit 6-B), 215 pcs.  Montepino Building:  3rd Floor     Frank Chavez Division (Unit 3-C), 40 pcs.     *Includes repainting of T-runners  Scope of Work:  1. The Contractor shall provide all materials, labor, equipment and tools, for the dismantling of the existing acoustic ceiling boards and installation of new acoustic ceiling boards for the OSG extension offices at APMC Building and Montepino Building.  2. The Contractor shall ensure all materials to be used for the installation of new acoustic ceiling boards are of good quality and subject for inspection by the OSG building administrator or its representative.  3. The Contractor shall be responsible for the dismantling of existing acoustic boards				

